

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division
Schedule -B

Name of Work: Improvements of RCC drain & Covering slab Dasarahalli Metro station to Bylappa Circle Right side road in Dasarahalli Ward No 15

SI	Description of Work	Unit	Qty	Sanctioned Rate	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Dismtling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismanlet material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specification Lime/Cement concrete I. By Manual Means C. Prestressed /Reinforced cement concrete Grade M-20 & above	Cum	265.44	1684.34	
2	Earthwork excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	911.82	189.74	
3	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	115.29	5421.90	
4	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification	Cum	306.36	7070.20	

EXECUTIVE ENGINEER-4
KRIDL, B&M DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER

Bruhat Bangalore Mahanagara Palike

D-1, Dasarahalli, Ward No. 15

5	Supplying and fixing precast reinforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	497.70	2208.00	
6	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications MORTH Specification No.1600 & 2200	Tonne	19.80	72326.98	
7	Providing and laying Pre cast drain cover slab of 250mm thickness including cost of all Materials Labour, curing, Transportation, Loading & unloading etc. as per direction of the Engineer Incharge	Sqm	78.75	5241.00	
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km	Cum	1177.26	69.80	

EXECUTIVE ENGINEER-4
SIGNALS & BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division